

SURVEY & REMONUMENTATION

JAN 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

97 DEC 23 PM 1:27
L.C. Records C.7 P. 127

REGISTER OF DEEDS

For corners in

_____ Iron _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>32W</u>	<u>C-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner Sec. 17, 18, 19, 20, T44N, R32W

I, Gary L. Pisoni, in a field survey on November 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1849 by Zelotes B. Searls, U.S. Deputy Surveyor.
Original Corner; Cedar Post
Original Bearing Trees;

White Pine	24"	S59° E	34 links (22.44 feet)
Cedar	18"	N60° W	38 links (25.08 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.


On 11-5-97, found a 2"x2" wooden stake painted blue marking the corner position. Found a location poster facing the corner position and an old dead 11" Balsam blazed as a BT and facing the stake. I accept the wood stake as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

In place of 2"x2" Wood Stake, set a 3/4" outside diameter aluminum rod monument, 4 feet long, 6 inches above ground, with a 3" aluminum cap stamped as follows; Iron County Remonumentation, T44N, R32W, S17, S18, S19, S20, 1997, RLS 27457; Blazed and scribed the following new bearing trees; (All measurements taken to a nail in side of tree)

Spruce	11"	N76° E	39.42 feet
Black Ash	9"	S10° E	48.26 feet
Balsam	6"	N65° W	41.40 feet
Balsam	8"	N18° W	26.29 feet
Steel Sign Post		S79° W	0.76 feet



PEER GROUP APPROVED

Gary L. Pisoni 11-11-97
IRON COUNTY REGISTERED LAND SURVEYOR

97-22
Signed by Gary L. Pisoni
Surveyor's Michigan License No. 27457

Date November 7, 1997