

SURVEY & REMONUMENTATION

JAN 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

97 DEC 23 PM 1:26

L.C. Records L.7 P.118

Eileen J. Stiles
REGISTERED DEEDS

For corners in

| | | |
|------------------------------------|----------------------------|---------------|
| <u>Iron</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>44N</u> R <u>R32W</u> | <u>D-3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner Section 5 and 8, T44N, R32W

I, Gary L. Pisoni, in a field survey on November 3, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | ● | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Zelotes B. Searls, U.S. Deputy Surveyor, in July of 1849.

Original Corner: Ironwood Post
Original Bearing Trees:

| | | | |
|-----|-----|--------|----------------------|
| Fir | 8" | S20° W | 22 links(14.52 feet) |
| Fir | 10" | N30° E | 19 links(12.54 feet) |

On 11-4-71, Arthur O. Enger, RLS with the Michigan Dept. Of Natural Resources, restored the corner position on line between the Section Corner 39.80 chains to the East and to the West. Set a 4 inch diameter aluminum capped pipe monument, 3 feet long, 12 inches above the ground. Recorded in Land Corner Certificate L. 1, Pages 189-190, on June 27th, 1973.

| | | | | |
|---------------------|----------|-----|--------|-----------|
| 1971 Bearing Trees; | S. Maple | 11" | N53° W | 17.1 feet |
| | S. Maple | 5" | N29° E | 17.4 feet |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

On 11-3-97 found the monument as set by Arthur O. Enger, and the following bearing tree:

| | | | |
|----------|----|--------|------------|
| S. Maple | 8" | N31° E | 17.38 feet |
|----------|----|--------|------------|

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

| | | | |
|-----------------|-----|--------|------------|
| S. Maple | 12" | S83° E | 12.40 feet |
| S. Maple | 7" | S12° W | 17.32 feet |
| S. Maple | 6" | N47° W | 6.84 feet |
| Steel Sign Post | | West | 0.95 feet |



FIELD GROUP APPROVED

Gary L. Pisoni 11-11-97
IRON COUNTY REPRESENTATIVE

97-13
Signed by *Gary L. Pisoni* Date November 7, 1997

Surveyor's Michigan License No. 27457