

SURVEY & REMONUMENTATION

JAN 13 1998

SECTION

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

97 DEC 23 PM 1:26

L.C. Records 1.7 P.124

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Gary L. Pisoni
REGISTER OF DEEDS

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>32W</u>	<u>D-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner Sec. 20 and 29, T44N, R32W

I, Gary L. Pisoni, in a field survey on November 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in July of 1849 by Zelotes B. Searls, U.S. Deputy Surveyor.
Original Corner; Sugar Post
Original Bearing Trees;

Sugar	12"	S76° E	10 links (6.60 feet)
Sugar	10"	N20° W	25 links (16.50 feet)

Billy D. Buckler, RLS with the Michigan Dept. Of Natural Resources, set a monument from original bearing tree evidence.

On 8-17-84, Keith L. Sackett, RLS with the Michigan Dept. Of Natural Resources restored the D.N.R. monument as set by Billy D. Buckler. Recorded in Land Corner Certificate L. 5, Page 81, on September 14th, 1984.
1984 Bearing Trees;

Maple	6"	N45° W	17.20 feet
Balsam	16"	N32° E	18.20 feet
Spruce	7"	S18° E	17.70 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 11-5-97 found monument as set by Billy D. Buckler;
1984 Bearing trees by Keith Sackett:

Sugar Maple	12"	N43° W	17.42 feet
Spruce	9"	S19° E	18.05 feet

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Balsam	8"	N57° E	37.05 feet
Ironwood	7"	S65° E	47.69 feet
Steel Sign Post		S14° E	0.95 feet

97-19
Signed by *Gary L. Pisoni* Date November 7, 1997
Surveyor's Michigan Licse No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS
REVISED MAY 14 1978
REVISED JAN 1983
REVISED OCT 1995

PEER GROUP APPROVED

Gary L. Pisoni 11-11-97
IRON COUNTY REGISTERED SURVEYOR

