

SURVEY & REMONUMENTATION

JAN 13 1998

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

For corners in

Iron SECTION
(County)

Located In:

Corner Code #

1. Public Land Survey

T 44N R 32W

E-7

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

97 DEC 23 PM 1:27

L.C. Records L17 P.132

Gailen Stobie
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Section Corner Common to Sections 16,17,20,21, T44N, R32W

I, Gary L. Pisoni, in a field survey on November 7, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Zelotes B. Searls, U.S. Deputy Surveyor, in July 1849.
Original Corner: Cedar Post
Original Bearing Trees:

White Pine	12"	S 74° E	23 links (15.18 feet)
Hemlock	10"	N 71° W	4 links (2.64 feet)

On 9/6/84, Keith L. Sackett, RLS with the Michigan Department of Natural Resources, found a 10"x10" squared concrete monument with a brass cap and located 4" above ground surface, stamped as follows: Wisconsin-Michigan Power Company, T44N, R32W, S-17, S-16, S-20, S-21.

DNR Bearing Trees 9/6/84 recorded in Land Corner Certificate L.5, page 94:

Balsam	4"	N 58° E	4.2 feet
Balsam	5"	S 16° W	14.3 feet
White Pine	18"	N 74° W	40.2 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

On 11/7/97, found monument as described above and the following bearing trees by Keith Sackett:

Existing Bearing Trees Found:

Balsam	6"	N 67° E	4.45 feet
Balsam	5"	S 16° W	14.46 feet
White Pine	18"	N 82° W	40.46 feet

Corner record research on file with County Representative.

PEER GROUP APPROVED

Gary L. Pisoni 11-11-97
IRON COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Spruce	6"	S 38° E	16.09 feet
Steel sign post		S 85° E	0.97 feet

97-27
Signed by Gary L. Pisoni Date November 8, 1997

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS

