

**SURVEY &
REMONUMENTATION**

JAN 13 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

97 DEC 23 PH 1:27
L.C. Records L.7 P.130

Richard J. Pisoni
REGISTERED DEEDS

For corners in

_____ Iron _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>32W</u>	<u>E-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner Sec. 20 and 21, T44N, R32W

I, Gary L. Pisoni, in a field survey on November 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1849 by Zelotes B. Searls, U.S. Deputy Surveyor.

Original Corner; Hemlock Post

Original Bearing Trees;

W. Pine	24"	S67° E	25 links (16.50 feet)
Sugar	10"	S06° W	14 links (9.24 feet)

On 11-13-84, Keith L. Sackett, RLS with the Michigan Dept. Of Natural Resources, restored the corner position at mid-point and on line between the Section Corner to the North and the Section Corner to the South. Set a 1"x32" Iron Pipe with a 4" aluminum cap. Recorded in Land Corner Certificate L.5, Page 99, on September 24th, 1985.

1984 Bearing Trees;

Maple	5"	N76° E	30.8 feet
Maple	4"	S70° E	24.6 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

On 11-5-97, found monument as set by Keith L. Sackett in 1984, and the following bearing trees;

Sugar Maple	8"	N81° E	30.83 feet
Sugar Maple	8"	S63° E	24.50 feet

PEER GROUP APPROVED

Gary L. Pisoni 11-11-97

IRON COUNTY REGISTERED DEEDS

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Sugar Maple	4"	S29° W	38.50 feet
Aspen	7"	N64° W	20.81 feet
Steel Sign Post		S32° E	0.70 feet

97-25
Signed by *Gary L. Pisoni*

Date November 7, 1997

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS IN JAN. 1971
REVISED MAY 1975
REVISED JAN., 1983
REVISED OCT., 1995

