

SURVEY & REMONUMENTATION

JAN 13 1998

SECTION

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

97 DEC 23 PH 1: 27

L.C. Records L.7 P. 136

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Gary L. Pisoni
REGISTER OF DEEDS

For corners in

| Iron (County) | Located In: | Corner Code # |
|------------------------------------|---------------------------|---------------|
| 1. Public Land Survey | T <u>44N</u> R <u>32W</u> | <u>G-6</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner between Sections 15 and 16

I, Gary L. Pisoni, in a field survey on November 10, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Zelotes B. Searls, U.S. Deputy Surveyor, in July 1849.
Original Corner: Maple Post
Original Bearing trees:

| | | | |
|---------|-----|--------|----------------------|
| Hemlock | 8" | S 48°W | 11 links (7.26 feet) |
| Sugar | 10" | N 61°E | 12 links (7.92 feet) |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

Corner located in an old popple clearcut.

Set quarter corner by single proportionate measurement on line between the NE and SE Section corners of Section 16.

Corner record research on file with County Representative.

PEER GROUP APPROVED
Gary L. Pisoni 11-11-97
IRON COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, set a 3/4" outside diameter aluminum rod monument, 3 feet long, 2" above ground surface with a 3" dia. aluminum cap stamped as follows: Iron County Remonumentation, T44N, R32W, 1/4, S-16, S-15, 1997, RLS 27457 from which I established the following blazed and scribed new bearing trees: (all measurements taken to a nail in side of tree)

| | | | |
|-----------------|------------|--------|------------|
| Red Maple | 11" | N 48°E | 87.00 feet |
| Red Maple | 10" | S 49°E | 38.50 feet |
| Rebar | 5/8" x 30" | N 74°W | 6.72 feet |
| Aspen | 8" | N 10°W | 12.17 feet |
| Steel sign post | | S 65°W | 0.70 feet |

97-31

Signed by Gary L. Pisoni Date November 11, 1997

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 22, 1975

