

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>44N</u> R <u>32W</u>	<u>J5</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u>11</u> T <u>44N</u> R <u>32W</u>	<u>15</u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Feb 14 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (J5) Quarter corner common to Sections 11-14. Reestablished in 1989 by K.L.Sackett, RLS midway and on line between Section corners. 1"IDx36" I.P. with 4" aluminum cap. 8" Spruce S24W 1.3', 7" Spruce S82E 7.0', 6" Spruce N24W 8.2'.
 (15-Sec. 11) West 1/16 between Sections 11 and 14. Corner recorded in 1989 by K.L.Sackett, RLS. Set 1"IDx32" IP with 4" aluminum cap. 7" Spruce S10E 9.8', 14" Spruce N41E 28.0', 16" R.Pine N01W 29.7'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J5) Recovered the 1989 monument in good condition and at record bearing and distance from the 1989 accessories as follows: 8" Spruce S19W 1.3', dead standing; 7" Spruce S82E 7.0', dead and down; 6" Spruce N24W 8.2', dead and down. Left the monument in place and made new accessories as described below.
 (15-Sec. 11) Found the 1989 monument in good condition and at record bearing and distance from the 1989 witnesses. The 1989 monument was placed in an erroneous position, S84W 252 feet from the position described herein. Established the corner midway and on a line of mean true bearing between Section corner 1315.25' west and Quarter corner 1315.25' east. Placed a new monument at the position thus established and destroyed the 1989 corner monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J5) Found 1"ID I.Pipe with 4" alum. MDNR cap. Blazed and scribed: 4" B.Spruce N25E 10.8' "1/4S NBT" 8" B.Spruce S77E 19.8' do 7" B.Spruce S5W 16.8' do 5" B.Spruce N31W 9.6' do Bearings are magnetic. Distances are to notch in lower blaze.	(15) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed: 8" W.Spruce N34E 26.3' "1/16S BT" 21" R.Pine S19E 41.7' do 8" W.Spruce S14W 19.5' do 7" Balsam N61W 11.0' do Bearings are magnetic. Distances are to notch in lower blaze.
---	--



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 2/28/02