

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Iron	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T <u>44N</u> R <u>32W</u>	<u>H3</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

May 13 2002

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3								●					
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(H3) Quarter corner common to Sections 3 and 10. Reestablished in 1989 by K.L.Sackett, RLS. 1"IDx32" iron pipe with 4" aluminum cap. 12" Tamarack N04W 13.8', 3" Balsam S50W 18.1', 3" Balsam S40E 13.6'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(H3) Recovered the 1989 monument, as described, in good condition, at record bearing and distance from the remaining two NBTs, both in good condition with markings visible. Left the monument in place and made new witnesses.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(H3) Found 1"ID I.pipe with 4" alum. MDNR cap. Blazed and scribed:  
 11" Tamarack N50W 23.6' "1/4S NBT"  
 7" B.Spruce S06E 28.9' do  
 the 1989 wits:  
 12" Tamarack N04W 13.9' notch visible  
 5" Balsam S54W 18.1' scribing visible  
 Bearings are magnetic. Distances are to notch in lower blaze.



Signed by *Stephan J. Szyszkoski*  
 Surveyor's Michigan License No. 33986

Date 6/10/02