

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>44N</u> R <u>32W</u>	<u>H4</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S <u>10</u> T <u>44N</u> R <u>32W</u>	<u>5</u>	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

May 13 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3								●					
4		7		8		9		●		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (H4) Center of Section 10. Not established in the original survey.
 (5-Sec. 10) North 1/16 corner Section 10. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H4) Established the corner at the intersection of straight lines connecting opposite quarter corners.
 (5-Sec. 10) Established the corner midway and on a straight line between Quarter corner 1319.83' north and Center of Section 1319.83' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed: 10" Sugar N20E 23.1' "C1/4 BT" 7" Sugar S51E 14.0' do 5" Sugar S06W 18.7' do 7" Sugar S72W 38.0' do Set squared cedar post adjacent. Bearings are magnetic. Distances to notch in lower blaze.	(5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed: 7" Sugar N19W 29.4' "1/16S BT" 5" Sugar N53E 26.8' do 4" Sugar S65E 15.0' do 14" Sugar S81W 8.0' do Set squared cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.
---	--



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/10/02