

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T ___ R ___	_____	_____
	T ___ R ___	_____	_____
	T ___ R ___	_____	_____
	T ___ R ___	_____	_____
2. Property Controlling in Section	S <u>10</u> T <u>44N</u> R <u>32W</u>	_____	8
	S <u>10</u> T <u>44N</u> R <u>32W</u>	_____	4
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____	_____
	S ___ T ___ R ___	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

May 13 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (8-Sec. 10) West 1/16 corner, Section 10. Not established in the original survey.
 (4-Sec. 10) Northwest 1/16 corner, Section 10. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (8-Sec. 10) Established the corner midway and on a straight line between Quarter corner 1317.32' west and Center of Section 1317.32' east.
 (4-Sec. 10) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed: 10" Maple N03W 38.6' "1/16S BT" 10" Maple S75E 17.3' do 6" Spruce S08W 34.8' do 3" Sugar N52W 38.5' do Set squared spruce post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.	(4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed: 6" Sugar N30E 33.9' "1/16S BT" 4" Sugar S68E 19.9' do 5" Dbl.Sugar S30W 21.1' do 7" Sugar N04W 27.3' do Set squared spruce post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.
--	---



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/10/02