

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Iron</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>44N</u> R <u>32W</u>	<u>H5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>9</u> T <u>44N</u> R <u>32W</u>	<u>3</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

3 May 09 2002  
 H5 May 08 2002

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(H5) Quarter corner common to Sections 10-15. Restablished in 1989 by K.L.Sackett, RLS, by single proportionate measurement to the original record. 1"IDx36" I.P. with 4" aluminum cap. 6" White Birch S27E 4.0', 10" White Birch N15E 26.5', 8" Balsam N66W 18.1'.  
 (3-Sec. 9) North 1/16 corner between Sections 8 and 9. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(H5) Recovered the 1989 monument, as described, in good condition, and at record bearing and distance from the two W.Birch NBTs, both in good condition with scribing still visible. Left the monument in place and made two new witnesses as described below.  
 (3-Sec. 9) Established the corner midway and on a line of mean true bearing between Section corner 1322.62' north and Quarter corner 1322.62' south.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(H5) Found 1"ID I.pipe with 4" alum. MDNR cap. Blazed and scribed: 5" Balsam N85E 27.3'                      "1/4S NBT" 5" Spruce N29W 48.6'                    do The 1989 wits: 9" W.Birch N18E 26.3' scribing visible 6" W.Birch S25E 4.0'                    do Bearings are magnetic. Distances are to notch in lower blaze.	(3) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed: 4" Maple N60E 30.1'                    "1/16S BT" 5" W.Spruce S60E 26.5'                do 8" W.Spruce S81W 19.4'                do 4" W.Birch N57W 1.1'                   do Squared a 5" W.Birch N53E 0.8' to center of tree. Bearings are magnetic. Distances are to notch in lower blaze.
---	--



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 6/10/02