

JAN 27 2005

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Table with columns: Iron (County), Located In: (Town, Range, Section), Corner Code #. Includes entries for Public Land Survey and Property Controlling in Section.

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims

Jan 13 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G12) Quarter corner common to Sections 33-34. 1984 - Reestablished by K.L. Sackett, RLS, midway and on line between Section corners. Set 1"IDx32" I.pipe with 4" alum. cap. 5" Sugar S05W 35.7', 4" Sugar N89E 17.3', 4" Maple S86W 5.3'. (14-Sec. 33) South 1/16 between Sections 33 and 34. 1984 - Established by K.L.Sackett, RLS, midway and on line between Section and Quarter corners. Set 1"IDx32" I.pipe with 4" alum. MDNR cap. 4" Balsam N07W 23.0', 5" Balsam S31W 61.5'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G12) Recovered the 1984 monument in good condition, at record bearing and distance from the Sugar NBT NE and Maple NBT SW, and in substantial accord with the record. Accepted same as a careful and faithful reestablishment of the position of the original corner. (14-Sec. 33) Recovered the 1984 monument in good condition, at record bearing and distance from the 1984 Balsam BT NW, and in substantial accord with the record. Accepted same as a careful and faithful determination of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G12) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nails in: 7" Sugar S87E 17.3' old marks visible \* 6" Maple S88W 5.4' old marks visible \* 6" Sugar in clump N24E 52.4' "1/4S NBT" 5" Spruce N78E 53.0' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. \* denotes 1984 NBT. (14) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nails in: 9" Balsam N03W 23.1' 1984 wit. 7" Balsam N35W 21.2' mrkd "1/16S BT" 4" Cherry N74W 30.2' do 7" Poplar S53E 23.9' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 and two black dots at grid intersections (33, 12) and (34, 13).



Signed by [Signature] Surveyor's Michigan License No. 33986

Date 1/18/05

For the Michigan Department of Natural Resources, Office of Land and Facilities