

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Iron</u> (County)	Located in:	Corner Code #	
1. Public Land Survey	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
2. Property Controlling in Section	S <u>33</u> T <u>44N</u> R <u>32W</u>	<u>13</u>	_____
	S <u>33</u> T <u>44N</u> R <u>32W</u>	<u>12</u>	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Jan 12 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- (13-Sec. 33) Southeast 1/16 corner, Section 33. Not established in the original survey.
- (12-Sec. 33) South 1/16 corner Section 33. Not established in the original survey.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (13-Sec. 33) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. The 1/16 corner to the north (corner #9) is not monumented at this time.
- (12-Sec. 33) Established the corner midway and on a straight line between Center of Section 1317.65' north and Quarter corner 1317.65' south. The position for the corner falls about 15' east of the C/L of a N-S dirt road, in ditch.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |   |   |
|---|---|
| (13) Set 1"IDx32" I.pipe with 4" alum.<br>MDNR cap. Set measuring nails in:<br>7" W.Spruce N59E 29.6' mrkd "1/16S BT"<br>12" W.Spruce S34E 33.3' do<br>14" W.Spruce N89W 15.5' do<br>12" W.Spruce N09W 37.0' do<br>Bearings are magnetic. Distances are to nail with tag. | (12) Set 1"IDx32" I.pipe with 4" alum.<br>MDNR cap, approx. 4" below grade. Set measuring nails in:<br>3" W.Birch N50E 19.7' mrkd "1/16S BT"<br>5" W.Spruce S55E 18.3' do<br>6" W.Spruce West 38.4' do<br>6" W.Spruce N76W 37.0' do<br>Bearings are magnetic. Distances are to nail with tag. |
|---|---|

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 1/18/05

For the Michigan Department of Natural Resources, Office of Land and Facilities