

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Iron	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	S ___ T ___ R ___	_____
2. Property Controlling in Section	S 33 T 44N R 32W	7
	S 33 T 44N R 32W	2
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Jan 13 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

- (7-Sec. 33) North 1/16 corner between Sections 33 and 34. 1984 - Established by K.L.Sackett RLS midway and on line between Section corner north and Quarter corner south. Set 1"IDx32" I.pipe with 4" aluminum cap. 9" Aspen S42W 11.3', 5" Aspen S24E 13.5'.
- (2-Sec. 33) East 1/16 corner between Sections 28 and 33. 1984: Established by K.L.Sackett RLS midway and on line between Section and Quarter corners. Set 1"IDx32" Iron pipe with 4" alum. cap. 7" Cherry N52W 26.6', 5" Poplar S30W 24.4', 5" Poplar S20E 14.8'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- (7-Sec. 33) Recovered the 1984 monument in good condition, at the record position, and accepted same as a careful and faithful determination of the position of the corner. Made new witnesses as described below.
- (2-Sec. 33) Recovered the 1984 monument in good condition, at the record position, and accepted same as a careful and faithful determination of the position of the corner. Made new witnesses as described below.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |   |   |
|---|---|
| (7) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nails in:<br>6" Maple clump S40E 42.0' mkd "1/16S BT"<br>6" Poplar N84E 11.4' do<br>5" Poplar N25E 5.3' do<br>3" Poplar N45W 15.7' do<br>Set squared cedar post adjacent.<br>Bearings are magnetic. Distances are to nail with tag. | (2) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nails in:<br>10" Poplar S33W 24.5' 1984 wit.<br>13" W.Pine S20W 142.7' mrd "1/16S BT"<br>3" Spruce S82W 54.9' do<br>4" Cherry N26E 42.3' do<br>Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. |
|---|---|



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 1/18/05

For the Michigan Department of Natural Resources, Office of Land and Facilities