

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> (County)	Located in:	Corner Code #	
1. Public Land Survey	T <u> </u> R <u> </u>	<u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>	<u> </u>
	S <u>22</u> T <u>44N</u> R <u>32W</u>	<u> </u>	<u>3</u>
2. Property Controlling in Section	S <u>22</u> T <u>44N</u> R <u>32W</u>	<u> </u>	<u>4</u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>	<u> </u>
4. Lot No. <u> </u> , Recorded Plat <u> </u>			
5. Private Claims			

Register of Deeds Stamp & File
Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on , 20 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(3-Sec. 22) North 1/16 corner between Sections 21 and 22. 1984 - Established by K.L.Sackett RLS midway and on line between 1/4 corner to south and Section corner to north. Set 1"IDx32" I.pipe with 4" aluminum cap. 8" Spruce S36W 20.2', 6" Maple N64W 34.1'.

(4-Sec. 22) Northwest 1/16 corner, Section 22. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


(3-Sec. 22) Found the 1984 monument in good condition and at record bearing and distance from the Maple BT NW, in good condition with overgrown blazes, and at record bearing and distance from the Spruce BT SW, now dead and down. The monument is 0.9' north and 1.0' east of the midway position between Quarter corner south and Section corner north and I accept the monument as a careful and faithful establishment of the position of the corner.

(4-Sec. 22) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(3) Fd. 1"ID I.pipe with 4" alum. MDNR cap.	(4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:	Set measuring nail with MDNR tag in the side of:
14" Maple N60W 34.5' old blazes (1984 BT)	8" Spruce N83E 20.5' mrkd "1/16S BT"
7" B.Spruce S10W 36.6' mrkd "1/16S BT"	10" twin Sugar S53E 43.8' do
4" Poplar S71W 27.2' do	5" twin Sugar S22W 16.6' do
5" Cherry N05W 20.0' do	7" Balsam N47W 10.8' do
Set sq'd spruce post adjacent. Bearings are magnetic.	Set sq'd cedar post adjacent. Bearings are magnetic.

Signed by *Stephan J. Szyszkoski*



Surveyor's Michigan License No. 33986

Date 12/12/07