

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>12</u> T <u>44N</u> R <u>32W</u>	<u>11</u>
	S <u>12</u> T <u>44N</u> R <u>32W</u>	<u>8</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on Jan 16, 2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- (11-Sec. 12) Southwest 1/16 corner, Section 12. Not established in the original survey.
- (8-Sec. 12) West 1/16 corner, Section 12. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (11-Sec. 12) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
- (8-Sec. 12) Established the corner midway and on a straight line between Quarter corner 1328.46' west and Center of Section 1328.46' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |  |  |
|--|--|
| (11) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.<br>Set measuring nail with MDNR tag in the side of:<br>8" Tamarack N35E 40.9' mrkd "1/16 BT"<br>4" Spruce S44E 11.4' do<br>12" Cedar S03W 48.7' do<br>7" Spruce S62W 22.5' do<br>Bearings are magnetic. Set sq'd post adjacent. | (8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.<br>Set measuring nail with MDNR tag in the side of:<br>16" Cedar N21W 12.95' mrkd "1/16S BT"<br>12" Cedar N72E 35.10' do<br>11" Cedar S22E 25.05' do<br>8" Cedar S73W 3.00' do<br>Bearings are magnetic. Set sq'd post adjacent. |
|--|--|

Signed by Stephan J. Szyszkoski



1/22/08

Surveyor's Michigan License No. 33986