

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Iron</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>    </u> R <u>    </u>		
	T <u>    </u> R <u>    </u>		
	T <u>    </u> R <u>    </u>		
2. Property Controlling in Section	S <u>12</u> T <u>44N</u> R <u>32W</u>		<u>9</u>
3. Miscellaneous Property in Sec.	S <u>12</u> T <u>44N</u> R <u>32W</u>		<u>13</u>
	S <u>    </u> T <u>    </u> R <u>    </u>		
	S <u>    </u> T <u>    </u> R <u>    </u>		
4. Lot No. <u>    </u> , Recorded Plat <u>    </u>			
5. Private Claims			

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on Jan 15, 2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- (9-Sec. 12) East 1/16 corner, Section 12. Not established in the original survey.
- (13-Sec. 12) Southeast 1/16 corner of Section 12. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- (9-Sec. 12) Established the corner midway and on a straight line between Center of Section 1320.61' west and Quarter corner 1320.61' east.
- (13-Sec. 12) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |   |  |
|---|--|
| <p>(9) Set 1"IDx32" I.pipe with 4" alum MDNR cap. The top center of the cap marks the corner position. The monument leans slightly to the NE. Set meas. nail with MDNR tag in the side of the following:<br/>         5" Sugar N11E 27.7' mrkd "1/16S BT"<br/>         22" W.Pine N46E 59.1' do<br/>         4" twin Maple S21E 23.4' do<br/>         7" Maple S17W 41.3' do<br/>         Bearings are magnetic. Set sq'd post adjacent. Monument was made firm in a mound of rock.</p> | <p>(13) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. The top center of the cap marks the corner position. The monument leans slightly to the NE. Set meas. nail with MDNR tag in the side of the following:<br/>         5" W.Spruce S84E 21.5' mrkd "1/16S BT"<br/>         11" Maple S08W 39.6' do<br/>         4" B.Spruce S53W 34.5' do<br/>         11" Maple clump N07W 38.5' do<br/>         Bearings are magnetic. Set sq'd post adj.</p> |
|---|--|

Signed by Stephan J. Szyszkoski



1/22/08

Surveyor's Michigan License No. 33986