

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S 12 T 44N R 32W	L4
	S 12 T 44N R 32W	12
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (L4) Center of Section 12. Not established in the original survey.
- (12-Sec. 12) South 1/16 corner, Section 12. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L4) Established the corner at the intersection of straight lines connecting opposite 1/4 corners. The Quarter corner L5 is not monumented. Its position was computed midway and on the Section line between Section corners K5 and M5. From the position thus established, I found a 1/2" dia. steel pin, not of record, placed by persons unknown, S52E 32.65' distant, which I did not accept as marking the position of the corner.

(12-Sec. 12) Established the corner midway and on a straight line between Center of Section 1323.06' north and the computed position for the 1/4 corner 1323.06' south (said position being midway and on the Section line between Section corners K5 and M5).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| (L4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of: | (12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of: |
| 12" Spruce N80E 56.35' mrkd "C1/4 BT" | 13" Cedar N84E 17.9' mrkd "1/16S BT" |
| 12" Spruce S40E 41.15' do | 11" Cedar S46E 20.3' do |
| 5" twin Y.Birch S09W 50.45' do | 9" Cedar S18W 42.6' do |
| 11" Maple N80W 48.15' do | 11" Cedar N16E 48.7' do |
| Bearings are magnetic. Set sq'd post adjacent. | Bearings are magnetic. Set sq'd post adjacent. |

Signed by Stephan J. Szyszkoski



1/22/08

Surveyor's Michigan License No. 33986