

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 44N R 32W	C3
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S T _____ R _____	_____
	S 7 T 44N R 32W	7
	S T _____ R _____	_____
3. Miscellaneous Property in Sec.	S T _____ R _____	_____
	S T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Stephan J. Szyszkoski, in a field survey on 7 01/27/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		●		8		9		10		11		12
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(C3) Corner common to Sections 5-6-7-8. 1997 - Recorded under Iron Co. Remonumentation in Liber 7, Page 121, Iron County L.C.R. 1" iron pipe with 4" aluminum MDNR cap set by A.O.Enger in 1971. 1997 witnesses: W.Spruce 7" N73W 53.85', Steel Sign Post N46E 0.87', 1971 bearing trees: W.Spruce 13" N26W 8.70', Balsam 11" N29E 13.29', Balsam 11" S28E 3.73'.

(7-Sec. 7) North 1/16 corner between Sections 7 and 8. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(C3) Found the monument as described, in good condition, and at record bearing and distances from the witnesses of record. The Balsam NE'ly is standing dead. Added one new witness.

(7-Sec. 7) Established the corner midway and on the Section line between Section corner 1320.18' north and Quarter corner 1320.18' south.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(C3) Found 1" ID I.pipe with 4" alum. MDNR cap. The 1997 witnesses of record check. Set measuring nail with MDNR tag in the side of: 9" Balsam N66E 30.8' mrkd "S5 NBT" Bearing is magnetic.

(7) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. The mon. leans to the NW due to rock. The top center of the cap marks the corner position. Set measuring nail with MDNR tag in the side of: 10" W.Spruce N10E 32.1' mrkd "1/16S BT" 5" Maple S81E 17.5' do 11" Maple S36W 7.6' do 6" Maple N12W 19.65' do Bearings are magnetic. Sq'd post adjacent.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 02/04/2010

For the Michigan Department of Natural Resources, Office of Land and Facilities

