

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>7</u> T <u>44N</u> R <u>32W</u>	<u>11</u>
	S <u>7</u> T <u>44N</u> R <u>32W</u>	<u>8</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 8 02/01/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(11-Sec. 7) Southwest 1/16 corner, Section 7. Not established in the original survey.

(8-Sec. 7) West 1/16 corner, Section 7. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(11-Sec. 7) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

(8-Sec. 7) Established the corner 20.00 chains, proportionate to the original record, west of the Center of Section 7 and on a straight line between the Center 1319.79' east and Quarter corner 1242.58' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(11) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 7" W.Spruce S81E 37.3' mrkd "1/16S BT"
 5" B.Spruce S16E 26.3' do
 6" W.Spruce S40W 19.4' do
 4" W.Spruce N02W 40.7' do
 Set sq'd post adjacent. Bearings magnetic.

(8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 7" W.Spruce N54E 16.5' mrkd "1/16S BT"
 5" B.Spruce S09E 25.6' do
 4" W.Spruce S73W 9.5' do
 10" W.Spruce N60W 25.0' do
 Set sq'd post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 02/04/2010

For the Michigan Department of Natural Resources, Office of Land and Facilities

