

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

| <u>Iron</u><br>(County)            | Located In:             | Corner Code # |
|------------------------------------|-------------------------|---------------|
| 1. Public Land Survey              | T _____ R _____         | _____         |
|                                    | T _____ R _____         | _____         |
|                                    | T _____ R _____         | _____         |
| 2. Property Controlling in Section | S 35 T 44N R 32W        | 11            |
|                                    | S 35 T 44N R 32W        | 9             |
|                                    | S _____ T _____ R _____ | _____         |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ | _____         |
|                                    | S _____ T _____ R _____ | _____         |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

11 04/27/2010

I, Stephan J. Szyszkoski, in a field survey on 9 04/28/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(11-Sec. 35) Southwest 1/16 corner, Section 35. Not established in the original survey.

(9-Sec. 35) East 1/16 corner, Section 35. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(11-Sec. 35) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

(9-Sec. 35) Established the corner midway and on a straight line between Quarter corner 1338.92' east and Center of Section 1338.92' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(11) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 10" Balsam N08E 4.4' mrkd "1/16S BT"  
 8" Poplar S05E 15.3' do  
 9" Poplar S63W 11.8' do  
 11" Poplar N29W 14.9' do  
 Set sq'd Cedar post adjacent.  
 Bearings are magnetic.

(9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 3" Cherry N15E 22.5' mrkd "1/16S BT"  
 3" Cedar S01W 17.1' do  
 9" Cedar S34W 29.0' do  
 12" Cedar S82W 47.7' do  
 Set sq'd Cedar post adjacent.  
 Bearings are magnetic.

Register of Deeds Stamp & File Number

|    | A | B  | C | D  | E | F  | G | H  | I | J  | K | L  | M |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 2  |   | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  |   | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  |   | 10 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  |   | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 |   | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 |   | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |   |    |   |    |   |    |   |    |   |    |   |    |   |

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 05/04/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division