

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 35 T 44N R 32W	12
	S 35 T 44N R 32W	16
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		16		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 12 04/29/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(12-Sec. 35) South 1/16 corner, Section 35. Not established in the original survey.

(16-Sec. 35) East 1/16 corner between Section 35 T44N-R32W and Section 2 T43N-R32W. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(12-Sec. 35) Established the corner midway and on a straight line between Quarter corner 1305.88' south and Center of Section 1305.88' north.

(16-Sec. 35) Established the corner midway and on the Township line between Section corner 1315.85' east and Quarter corner 1315.85' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 8" B.Ash N45E 12.2' mrkd "1/16S BT"
 12" Cedar N89E 25.7' do
 7" twin B.Ash S47E 3.7' do
 6" twin B.Ash S83W 3.8' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

(16) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 7" B.Ash N24E 30.3' mrkd "1/16S BT"
 7" B.Ash N86E 35.6' do
 4" Sugar S39E 17.1' do
 4" Sugar N36W 5.5' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 05/04/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division