

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY  
T 43-44N R 33W

DESCRIPTION OF CORNER Section Corner 1, 2, 35 and 36

CORNER MONUMENT 1" I.D. x 11" iron pipe with a 1/2" x 12" iron crossbar at bottom end to anchor it.

DATE MONUMENT PLACED AND WITNESSED April 24, 1970

WITNESSES TO CORNER..... NBT's (All Shadko's; distances to head of 60d nail on side of tree)



Y. Birch	12	S24 $\frac{1}{2}$ °W	47.73 ft.
Maple	6	N47 $\frac{1}{2}$ °W	46.47 ft.
* Maple	5	N37 $\frac{1}{2}$ °E	39.11 ft.
** Elm	14	S73°E	65.44 ft.

AND \* Now dead  
\*\* Now cut down and removed.

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 4" x 36" concrete filled iron pipe with MDNR Fisheries Division brass identification marker set by G. A. Shadko, R.L.S. No. 1934 on 11/2/62, in the center of an E & W county road. Shadko had placed monument in center of road in line with old fences running to north and south. Monument found frost-heaved out of road bed. Placed a plain iron pipe in road, and re-set Shadko's monument 32.50 feet north of it for a witness corner.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

*Arthur O. Enger*  
REGISTERED LAND SURVEYOR  
Arthur O. Enger

DATE August 24, 1971

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68