

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 NR. 33 W.

Iron COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sec. 's 2-11

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 10" W. Pine S 36° E 54 links
"1/4 S HBT"
8" Cedar N 49° W 12 links
"1/4 S HBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Set 1/4 corner on edge of swamp on old E-W cutting line.

Found numerous blazes both east and west along this line. Some blazes are 25 years old.

Distance agrees with swamp edge, stream and other corners east of 1/4 corner.

No positive evidence of tamarack or fir B.T.'s.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 6/6/57
REGISTERED LAND SURVEYOR