

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 NR. 32-33 W

Iron COUNTY

DESCRIPTION OF CORNER Section Corner common to Sec.'s 6-7-1-12

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 24" W. Pine stump S 22° W 76½ links

"S 12 NBT"

8" W. Spruce S 30° E 73½ links

"S 7 NBT"

5" Aspen N 20° E 50 links

"S 6 NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced corner from two white pine B.T.'s bearing N 12° E 30 links and S 70° E 13 links, both stumps burned badly and rotted. Trace of scars on both stumps.

Cruisers blades on NE stump, found by Forestry Division Survey Crew. Found white pest about 2 chs. south of corner.

SURVEYORS SEAL

SIGNED

Billy D. Buckles
REGISTERED LAND SURVEYOR

DATE

6/6/57