

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 NR. 33 W.

Iron COUNTY

DESCRIPTION OF CORNER Section corner common to Sec.'s 1-2-11-12

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER	5" Cedar	S 88° E	18 1/2 links
		"S 12 NBT"	
	5" Tamarack	N 75° W	25 links
		"S 2 NBT"	
	9" Cedar	S 12° E	62 links
		"S 12 NBT"	

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established section corner by double proportionate measure from corners in 4 directions.

Section Corner 1 mile east.  
Section Corner 1 mile north  
Section Corner 1 mile south  
1/4 corner 1/2 mile west

Site of possible tamarack B.T. N 78° E 24 links.

Found old squared cedar 65 links east. Cutting edge going west from corner.

SURVEYORS SEAL

SIGNED

*Billy D. Buckler*  
REGISTERED LAND SURVEYOR

DATE 6/7/58