

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES


LAND CORNER RECORD

Iron COUNTY  
T 43-44N R 33W

DESCRIPTION OF CORNER Section Corner 2, 3, 34, and 35  
CORNER MONUMENT 3½"x42" concrete-filled iron pipe capped with Conservation Dept.  
brass identification plate. Witnesses by Shadko:

DATE MONUMENT PLACED AND WITNESSED April 17, 1972

WITNESSES TO CORNER..... Cedar 11 N41°E 19.54 ft. (to 60d spike in SE base of tree)



Cedar 9 N74°W 39.72 ft. (to 60d spike in base of tree)

Cedar 14 S70°W 4.6 ft. (probably to spike in W base of tree)

AND

Spruce 13 S49°E 48.45 ft. (to R.R. spike on SW side of tree)

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner perpetuated by G. A. Shadko, R.L.S. No. 1934, on 11/1/62, whose records indicate he identified two original cedar bearing trees and placed the monument indicated below.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor

SIGNED

*Arthur O. Enger*  
REGISTERED LAND SURVEYOR  
Arthur O. Enger

DATE June 27, 1972