

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 44 N. R. 33 W.	L1
2. PROPERTY CONTROLLING IN SECTION 1	T. 44 N. R. 33 W.	1
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on September 8 19 71, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19 \_\_\_\_\_ found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner L1:** Cherry post (not found)  
 Spruce 8 N41E 14 " "  
 Fir 8 N60W 21 " "  
 Found a L.E.S. approximate corner post S10°W 83.6 ft.

**Corner 1:** Not established in original survey and subsequently only by a forester's approximate corner.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner L1:** The L.E.S. post is too far off to be believable, and DNR records indicate these posts as not being intended to mark the true corners. Therefore, re-established the corner on line between Sec. Corners 39.986 ch. to E and to W.

**Corner 1:** Established on line between Sec. Cor. 19.993 ch. W and 1/4 corner 19.993 ch. E.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Monuments for both corners:** 1" I.D. x 36" iron pipe with 4" aluminum cap.

**Witnesses for Corner L1:** W. Birch 14 N65°E (mag.) 18.0 ft. "1/4S, NBT"  
 (Variation 1°40' East) R. Maple 14 S64°W (mag.) 20.5 ft. "1/4S, NBT"

**Witnesses for Corner 1:** R. Maple 6 S51°E (mag.) 34.5 ft. "1/16S, BT"  
 (Variation 1°50' East) W. Pine 21 S86°W (mag.) 38.0 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE February 13, 1973  
MICHIGAN REGISTERED LAND SURVEYOR

**Michigan Department of Natural Resources**

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581