

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	(IRON COUNTY) LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. <u>X</u> , R. <u>33</u> <u>X</u> W.	C-9
2. PROPERTY CONTROLL- 19 _____ ING IN SECTION _____	T. <u>44</u> N. <u>X</u> , R. <u>33</u> <u>X</u> W.	14 & 14a
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. _____ W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on See below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner C9 (Section Corner 19, 20, 29, & 30, T44N, R33W):
 Wood post (Not found. Found 1" O.D. x 42" drill rod in place.)
 Y. Birch 20 N16E 13 (Not found. No subsequent accessories found.)
 Sugar 18 S70W 64 (Not found. No subsequent accessories found.)

Corner 14 (South 1/16 corner between Sections 19 & 20, T44N, R33W):
 Not established in original survey. Found 3/4" I.D. x 18" iron pipe in place.

Corner 14a (South M.C. between Sections 19 & 20, T44N, R33W):
 Wood post (Not found. Found 1" O.D. x 16" iron pipe in place.)
 Y. Birch 4 S52E 29 (Not found. No subsequent accessories found.)
 Cedar 8 S53W 25 (Not found. No subsequent accessories found.)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner C9: On 9-22-78, replaced drill rod with mon. shown below. Origin of rod unknown, but probably set from incomplete original survey evidence. A number of M/B descriptions on Fire Lake apparently are tied to it and to other monuments mentioned in this report, so thought it best not to disturb these descriptions, especially as it is hard to prove that the original corner stood indubitably in some other location. **Corner 14:** On 9-22-78, replaced found mon. with new mon. shown below. Corner was doubtless intended to be prop. on line bet. Sec. Cor. to S and M.C. to N, but was found to be S34°17'W 1.23 ft. from that position. Distance S to Sec. Cor. is 19.73° ch. and N to M.C. is 12.112 ch. **Corner 14a:** On 5-7-79, replaced found mon. with new mon. shown below. History of found mon. not known.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New monuments for all 3 corners: 1" I.D. x 36" iron pipes with 3 3/4" aluminum caps.

Witnesses for Corner C9: Sugar Maple 7 S83°E (mag.) 13.1 ft. "S29, NBT"
 Declination 4°30' East. Sugar Maple 9 S37°W (mag.) 26.4 ft. "S30, NBT"

Witnesses for Corner 14: Sugar Maple 5 N67°W (mag.) 20.7 ft. "1/16S, BT"
 Declination 1°20' East. Sugar Maple 4 N 6°E (mag.) 11.5 ft. "1/16S, BT"
 Distances horizontal.

Witnesses for Corner 14a: Sugar Maple 8 S14°E (mag.) 15.3 ft. "MC, NBT"
 W. Birch 9 N78°W (mag.) 23.4 ft. "MC, NBT"

SIGNED BY _____ DATE _____

Carl R. Johnson

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE February 11, 1980

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

