

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(IRON COUNTY)

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. <u>X</u> , R. <u>33</u> W.	<u>#C-7</u>
2. PROPERTY CONTROLLING IN SECTION <u>19</u>	T. <u>44</u> N. <u>X</u> , R. <u>33</u> W.	<u>#7 and 7a</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on See below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

**Corner C7 (Section Corner 17, 18, 19, & 20, T44N, R33W):**

Wood post (Not found. Found 1" iron pipe with brass cap in place.)

Y. Birch 18 S81E 27 (Not found. No subsequent accessories found.)

Hemlock 20 N81W 38 (Not found. No subsequent accessories found.)

**Corner 7 (North 1/16 corner between Sections 19 & 20, T44N, R33W):**

Not established in original survey nor subsequently, apparently.

**Corner 7a (North M.C. between Sections 19 & 20, T44N, R33W):**

Wood post (Not found. No subsequent monuments found.)

Cedar 8 N60E 25 (Not found. No subsequent accessories found.)

Cedar 5 N50W 17 (Not found. No subsequent accessories found.)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

**Corner C7:** On 8-6-79 witnessed monument as found set by unknown persons from unknown evidence.

There are some discrepancies in distances to lake edge E and S as compared to original record, and with alignment with N & S road to N, but as I cannot demonstrate any other place to be the original corner position, I have concluded to accept the monument as the corner it purports to be.

**Corner 7:** Established 4-26-79 proportionately on line between Sec. Cor. 20.020 ch. N and lake edge on sec. line 8.91 ± ch. S. (Not proportioned from M.C. monument, which is 8± links N of lake edge).

**Corner 7a:** Restored 5-7-79 on true sec. line on N edge of Fire Lake, 28.931 ch. S of Sec. Cor. and 10.429 ch. N of 1/4 cor. in lake. (Mon. is 28.854 ch. S of Sec. Cor. and 10.506 ch. N of 1/4 cor. in lake).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**Corner C-7:** 1" I.D. iron pipe (length unknown) with 2 1/8" brass cap.

W. Birch 4 N18°W (mag.) 37.6 ft. "S18, NBT"

R. Maple (Twin) 9 N53°E (mag.) 56.7 ft. "NBT"

Declination is 3°00' East.

**Corner 7:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.

Red Maple 6 S76°W (mag.) 5.1 ft. "1/16S, BT"

Red Maple 4 N 6°W (mag.) 14.3 ft. "1/16S, BT"

Declination is 2°25' East.

**Corner 7a:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.

Tamarack 9 N26°E (mag.) 40.3 ft. "MC, NBT"

Tamarack 5 N58°W (mag.) 28.8 ft. "MC, NBT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

Carl R. Johnson

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE January 25 1980

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

