

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	(IRON COUNTY) LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. <u>X</u> R. <u>33</u> W.	<u>#F-7 & G-7</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner F7 (1/4 corner between Sections 16 & 21, T44N, R33W):
 Wood post (Not found. Found 12" well-point in place.)
 Sugar 16 N40E 10 (Not found. MSDH reference tags found nearby.)
 Fir 10 S14E 15 (Not found. MSDH reference tags found nearby.)

Corner G7 (Section Corner 15, 16, 21, & 22, T44N, R33W):
 Wood post (Not found. Found steel axle shaft in place.)
 W. Pine 36 N36W 27 (Not found. No subsequent accessories found.)
 Sugar 6 S34E 23 (Not found. No subsequent accessories found.)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner F7: On 8-6-79 replaced found monument with monument described below. Well-point evidently in place for many years, and apparently used by State Highway Department and others. Origin unknown. Alined with centerline of county road to east, and bears N88°51.4'W 39.813 ch. from a mon. at road intersection to East, the record distance being 40.29 ch.

Corner G7: On 7-20-78 witnessed a 1.1" diameter steel axle shaft of unknown length found buried vertically in road bed at intersection of E & W road CL and W edge of road going N. Also alined with fence going S. Assumed to be the sec. corner by common report, although the history is not known by the undersigned.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner F7: 1" I.D. x 24" iron pipe with 3 3/4" aluminum cap.
 Power Pole #85-8 S12°E (mag.) 40.45 ft. (to a nail with MSHD brass tag).
 Steel Stop-Sign Post N9°E (mag.) 85.90 ft.
 SE cor. of house foundation N82°32'W (true) 128.76 ft.
 NE cor. of house foundation N54°57'W (true) 157.96 ft.
 Declination is 4°30' East.

Corner G7: 1.1" diameter steel axle shaft, buried beneath road surface.
 Power Pole #N63-231 S26°W (mag.) 35.08 ft. (to a nail with DNR brass ref. marker);
 5-sided nut on the W'y of 2 water shut-off boxes N68°E (mag.)
 47.79 ft. (to punch mark in center of nut).

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE January 25, 1980
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

