

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	(IRON COUNTY) LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. R. <u>33</u> E. W.	#C-4; C-5; E-5
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner C4 (1/4 corner between Sections 7 & 8, T44N, R33W) and
 Corner C5 (Section Corner 7, 8, 17, & 18, T44N, R33W) and
 Corner E5 (Section Corner 8, 9, 16, & 17, T44N, R33W):

Original monuments and accessories irrelevant, as these corners all fall in county roads and any evidence has long since disappeared.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner C4: On 4-14-77 monumented as shown below a point at the intersections of CL's of E & W and N & S roads, as determined from old fence lines paralleling each road on each of their edges, said point presumed to be the corner by common report.

Corner C5: On 4-14-77 monumented as shown below a point similar to, and under the same circumstances as, the point mentioned for Corner C4.

Corner E5: On 8-24-78 witnessed a monument as shown below, found in place in approx. CL of an E & W county road, and with old farm fences running to N and to S from it. Appears old and commonly used as the corner it purports to be. Bears N89°37'E 5224.37 ft. (by EDM) from monument reported for Corner C5, the record distance being 5247.66 ft.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner C4: 8" galvanized gutter spike, buried 6" deep in road-bed.
 Power Pole #N71-1360 S50°W (mag.) 43.92 ft. (to a tack)
 Balm-of-Gilead 24 N56°E (mag.) 50.45 ft. (to a nail)

Corner C5: 8" galvanized gutter spike, buried 6" deep in road-bed.
 Power pole S26°W (mag.) 58.38 ft. (to a tack)
 Stop-sign steel post N59°E (mag.) 40.25 ft.

Corner E5: 3/4" iron rod of unknown length, buried in road-bed.
 Power Pole #N38-2943 S47 1/2°E (mag.) 44.78 ft.
 Red Pine 6 N22°W (mag.) 39.50 ft.
 Distances are to a nail with brass D.N.R. reference tag.
 Declination is 2°35' East.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE January 20, 1980
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 13581