

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

IRON COUNTY

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>44</u> N. <u>X</u> R. <u>33</u> K. <u>W.</u>	<u>12</u>
2. PROPERTY CONTROLLING IN SECTION	<u>2</u> T. <u>44</u> N. <u>X</u> R. <u>33</u> K. <u>W.</u>	<u>15, 3, 10</u>
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ R. _____ E. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 14, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner 15: Not set on original survey nor subsequently apparently.
- Corner 3: Not set on original survey nor subsequently apparently.
- Corner 10: Not set on original survey nor subsequently apparently.
- Corner 12: Original monument and accessories not found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner 15: Established midway and on line between quarter corner east and section corner west.
- Corner 3: Established by proportion on line between section corner north and quarter corner south.
- Corner 10: Established midway and on line between quarter corner north and section corner south.
- Corner 12: Restored by proportion on line between section corners north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| <p>Corner 15: Set 1" I.D. by 32" I.P. w/4" alum. cap.
20" w. pine N12W 43.4' 1/16S, BT
6" cedar N57E 23.5' 1/16S, BT</p> <p>Corner 3: Set 1" I.D. by 32" I.P. w/4" alum. cap.
8" y. birch N48W 10.0' 1/16S/BT
9" sugar N48E 16.1' 1/16S, BT
11" cedar S36E 51.5' 1/16S, BT</p> | <p>Corner 10: Set 1" I.D. by 32" I.P. w/4" alum. cap.
6" cherry N44W 5.8' 1/16S, BT
9" spruce S38W 6.2' 1/16S, BT
12" balsam N78E 7.3' 1/16S, BT</p> <p>Corner 12: Set 1" I.D. by 32" I.P. w/4" alum. cap.
12" sugar N58W 14.0' 1/4S, NBT
6" sugar N42E 19.1' 1/4S, NBT
12" sugar S52E 9.4' 1/4S, NBT</p> |
|--|---|

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE _____

CHIEF OF SURVEY PARTY
Keith L. Sackett
MICHIGAN REGISTERED LAND SURVEYOR
Keith L. Sackett
Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

