

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	<u>IRON COUNTY</u> LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> <sup>N.</sup> / <sub>X.</sub> R. <u>33</u> <sup>X.</sup> / <sub>W.</sub>	B-9 & C-10
2. PROPERTY CONTROLLING IN SECTION <u>19</u>	T. <u>44</u> <sup>N.</sup> / <sub>X.</sub> R. <u>33</u> <sup>X.</sup> / <sub>W.</sub>	16
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ <sup>N.</sup> / <sub>S.</sub> R. _____ <sup>E.</sup> / <sub>W.</sub>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner B9 (1/4 corner between Sections 19 & 30, T44N, R33W):**

- Wood post (Not found. No subsequent monuments found.)
- Sugar 10 N36W 33 (Not found. No subsequent accessories found.)
- Sugar 12 S50E 05 (Not found. No subsequent accessories found.)

**Corner C10 (1/4 corner between Sections 29 & 30, T44N, R33W):**

- Wood post (Not found. No subsequent monuments found.)
- Sugar 10 N48W 40 (Not found. No subsequent accessories found.)
- Sugar 14 S48E 60 (Not found. No subsequent accessories found.)

**Corner 16 (East 1/16 corner between Sections 19 & 30, T44N, R33W):** Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner B9:** Restored 5/4/78 proportionately on line (true bearing of section line is S88°30' W) between Sec. Corners 40.043 ch. E and 39.584 ch. W. Found a Northern Paper Mills location tag on a 6" maple N68°E 35.8 ft.

**Corner C10:** Restored 9/22/78 on line between Sec. Corners 40.3275 ch. to N and to S.

**Corner 16:** Established 9/11/78 on line between Sec. Cor. 20.0215 ch. E and 1/4 cor. 20.0215 ch. W.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Monuments for all 3 corners:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap

**Witnesses for Corner B9:** Sugar Maple 6 N 69°W (mag.) 20.5 ft. "1/4S, NBT"  
Declination 2°30' East. Sugar Maple 7 S 48°E (mag.) 29.3 ft. "1/4S, NBT"

**Witnesses for Corner C10:** Triple Sugar Maple 12 N34°E (mag.) 19.7 ft. "1/4S, NBT"  
Declination 1°00' East. Double Sugar Maple 11 S12 1/2°E (mag.) 21.9 ft. "1/4S, NBT"

**Witnesses for Corner 16:** Basswood (NW'ly of Triple 8") S47°W (mag.) 23.0 ft. "1/16S, BT"  
Declination 2°00' East. Sugar Maple 4 S8°E (mag.) 11.6 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE March 15, 1979  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

