

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	<u>IRON COUNTY</u> LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> <sup>N.</sup> / <sub>S.</sub> , R. <u>33</u> <sup>X.</sup> / <sub>W.</sub>	B-11 & C-11
2. PROPERTY CONTROLLING IN SECTION <u>31</u>	T. <u>44</u> <sup>N.</sup> / <sub>S.</sub> , R. <u>33</u> <sup>X.</sup> / <sub>W.</sub>	2
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ <sup>N.</sup> / <sub>S.</sub> , R. _____ <sup>E.</sup> / <sub>W.</sub>	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 11, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

**Corner B11** (1/4 corner between Sections 30 & 31, T44N, R33W):

- Wood post (Not found. See B for subsequent monuments.)
- Hemlock 30 N35E 10 (Not found. No subsequent accessories found.)
- Sugar 12 S17W 86 (Not found. No subsequent accessories found.)

**Corner C11** (Section Corner 29, 30, 31, & 32, T44N, R33W):

- Wood post (Not found. No subsequent monuments found.)
- Sugar 16 S50W 37 (Not found. No subsequent accessories found.)
- Sugar 8 N30E 12 (Not found. No subsequent accessories found.)

**Corner 2** (East 1/16 corner between Sections 30 & 31, T44N, R33W): Not established in original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

**Corner B11:** Restored proportionately on line (true bearing S88°55'W) between Sec. Corners 39.855 ch. E and 39.465 ch. W. Found a recent 3" x 3" x 5' squared maple post S58°W 47.0 ft. and a 16" cedar with older blazes on 4 sides S5°E 93.2 ft. for approximate corners.

**Corner C11:** Restored proportionately bet. Sec. Corners 80.655 ch. to N and to S and at record distance of 79.32 ch. E of Sec. Cor. on W. twp. boundary. Based on measurements E to a stream, swamp edges, ridges, and a pond, there appears to be an error in the original survey measurements in the E half mile of the line between 29 & 32, thus proportion E & W did not seem proper to use.

**Corner 2:** Established on line between Sec. Cor. 19.9275 ch. E and 1/4 cor. 19.9275 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Monuments for all 3 corners: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
- Witnesses for Corner B11: Sugar Maple 11 N38°W (mag.) 45.8 ft. "1/4S, NBT"  
Declination 0°55' East. Sugar Maple 4 S86°E (mag.) 20.2 ft. "1/4S, NBT"  
Cedar 16 S 8°W (mag.) 26.7 ft. "1/4S, NBT"
- Witnesses for Corner C11: Sugar Maple 10 S40°W (mag.) 13.0 ft. "1/4S, NBT"  
Declination 1°20' East. Sugar Maple 11 S25°E (mag.) 22.3 ft. "1/4S, NBT"  
Sugar Maple 6 N74°E (mag.) 18.0 ft. "1/4S, NBT"
- Witnesses for Corner 2: Sugar Maple 6 S15°W (mag.) 21.2 ft. "1/16S, BT"  
Declination 0°20' East. W. Pine 24 S48°E (mag.) 28.7 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE March 12, 1979

CHIEF OF SURVEY PARTY  
Arthur O. Enger  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

