

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	<u>IRON COUNTY</u> LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. <u>X.</u> R. <u>33</u> W. <u>X.</u>	C-12
2. PROPERTY CONTROLLING IN SECTION <u>32</u>	, T. <u>44</u> N. <u>X.</u> R. <u>33</u> W. <u>X.</u>	3 & 10
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 20, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner C12 (1/4 corner between Sections 31 & 32, T44N, R33W):
 Wood post (Not found. No subsequent monuments found.)
 Sugar 10 N44W 26 (Not found. No subsequent accessories found.)
 Sugar 10 S27E 31 (Not found. No subsequent accessories found.)

Corner 3 (North 1/16 corner between Sections 31 & 32, T44N, R33W) and

Corner 10 (South 1/16 corner between Sections 31 & 32, T44N, R33W):

Neither of these corners established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner C12: Restored on line between Sec. Corners 40.3275 chains to N and to S.

Corner 3: Established on line between Sec. Cor. 20.164 ch. N and 1/4 cor. 20.164 ch. S.

Corner 10: Established on line between Sec. Cor. 20.164 ch. S and 1/4 cor. 20.164 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all 3 corners: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
Witnesses for Corner C12: Sugar Maple 9 N22°E (mag.) 7.1 ft. "1/4S, NBT"
 Declination 0°50' East. Sugar Maple 7 N83°W (mag.) 18.7 ft. "1/4S, NBT"

Witnesses for Corner 3: Sugar Maple 14 S54°W (mag.) 22.8 ft. "1/16S, BT"
 Declination 1°00' East. W. Pine 32 S25°E (mag.) 29.3 ft. "1/16S, BT"

Witnesses for Corner 10: Cedar 12 N80°W (mag.) 23.0 ft. "1/16S, BT"
 Declination 0°45' East. Cedar 10 S20°E (mag.) 25.9 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 13, 1979

CHIEF OF SURVEY PARTY
Arthur O. Enger
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

