

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	<u>IRON COUNTY</u> LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. <u>33</u> W. <u>X</u>	E-11
2. PROPERTY CONTROLLING IN SECTION <u>32</u>	, T. <u>44</u> N. <u>33</u> W. <u>X</u>	2
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ S., R. _____ E. _____ W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner Ell (Section Corner 28,29,32&33, T44N, R33W):
 Wood post (Not found. No subsequent monuments found.)
 Sugar 16 S75E 49 (Not found. No subsequent accessories found.)
 Aspen 6 N80W 10 (Not found. No subsequent accessories found.)

Corner 2 (East 1/16 corner between Sections 29 & 32, T44N, R33W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner Ell: Restored 9/21/78 proportionately (as determined partly from aerial photos of which the scale had been determined by ground measurements) on line between Sec. Corners 80.391 ch. S and 80.391 ch. N, in accordance with the method used in the original survey subdivision. Manifest errors in the original measurements of the line between Secs. 29 & 32, as evidenced by comparison of record measurements to natural features with current measurements, show that an E & W proportion would not be reliable as an indicator of the original position of this corner.

Corner 2: Established 9/22/78 on line between Sec. Cor. 19.534 ch. E and 1/4 cor. 19.534 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner Ell: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Twin W. Spruce 6 S24°W (mag.) 38.1 ft. "S32, NBT"
 Black Spruce 6 S70°E (mag.) 6.9 ft. "S33, NBT"
 Red Pine 6 N62°W (mag.) 6.8 ft. "S29, NBT"
 Declination 1°20' East.

Corner 2: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 W. Spruce 6 N66°E (mag.) 15.6 ft. "1/16S, BT"
 B. Spruce 6 S89°W (mag.) 19.7 ft. "1/16S, BT"
 Declination 0°55' East.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 15, 1979

CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

