

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	<u>IRON COUNTY</u> LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>44</u> N. <u>X</u> , R. <u>33</u> <u>X</u> W.	E-12
2. PROPERTY CONTROLLING IN SECTION <u>32</u>	, T. <u>44</u> N. <u>X</u> , R. <u>33</u> <u>X</u> W.	7 & 14
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____, R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 21, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E12 (1/4 corner between Sections 32 & 33, T44N, R33W):
 Wood post (Not found. No subsequent monuments found.)
 W. Pine 14 N67W 46 (Not found. No subsequent accessories found.)
 Cedar 12 S76E 12 (Not found. No subsequent accessories found.)

Corner 7 (North 1/16 corner between Sections 32 & 33, T44N, R33W) and

Corner 14 (South 1/16 corner between Sections 32 & 33, T44N, R33W):

Neither of these corners established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E12: Restored on line between Sec. Corners 40.197 ch. to N and to S.

Corner 7: Established on line between Sec. Cor. 20.098 ch. N and 1/4 cor. 20.098 ch. S. Corner falls on top of a high narrow ridge NE & SW.

Corner 14: Established on line between Sec. Cor. 20.098 ch. S and 1/4 cor. 20.098 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all 3 corners: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.

Witnesses for Corner E12: W. Spruce 10 N82°E (mag.) 28.1 ft. "1/4S, NBT"

Declination 0°55' East. R. Pine 8 N15°W (mag.) 26.8 ft. "1/4S, NBT"

Witnesses for Corner 7: Red Maple 7 N45°E (mag.) 29.0 ft. "1/16S, BT"

Declination 1°00' East. Red Maple 5 S20°E (mag.) 26.6 ft. "1/16S, BT"

Witnesses for Corner 14: *W. Pine Stump 24 N78°E (mag.) 73.1 ft. "1/16S, BT"

Declination 0°45' East. W. Pine Stump 30 S58°E (mag.) 101.1 ft. "1/16S, BT"

*Aluminum location tag on this stump.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 15 1979
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

