

SURVEY & REMONUMENTATION

JAN 19 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

_____ Iron _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>33W</u>	<u>A-3</u> ✓
	T <u>44N</u> R <u>34W</u>	<u>M-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY MICHIGAN
RECEIVED FOR RECORD

98 DEC 28 AM 11:21
L.C. Records: L. 7, P. 293
Gary L. Pisoni

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner Sections 6 and 7, T44N, R33W
Section Corner Sections 1 and 12, T44N, R34W

I, Gary L. Pisoni, in a field survey on Nov. 20, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														
2	6			5			4			3			2	1
3														
4	7			8			9			10			11	12
5														
6	18			17			16			15			14	13
7														
8	19			20			21			22			23	24
9														
10	30			29			28			27			26	25
11														
12	31			32			33			34			35	36
13														

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1846 by Austin Burt, U.S. Deputy Surveyor.

Original Corner; Cedar Post

Original Bearing Trees:

Sugar	14"	S 72° W	43 links (28.38 feet)
Cedar	11"	N 53° E	16 links (10.56 feet)

On June 24, 1851, Guy H. Carleton, U.S. Deputy Surveyor, made two new bearing trees:

Fir	12"	N 32° W	42 links (27.72 feet)
Yellow Birch	16"	S 51° E	12 links (7.92 feet)

On 6/6/77, Arthur O. Enger, RLS with Michigan Dept. of Natural Resources restored the corner position at the intersection of County roads running East & West and North & South. He set a 3 3/4" diameter aluminum capped pipe monument 1 1/2" below asphalt surface; recorded in L.C. Certificate, Liber 1, Pages 486 on 8/5/77.

1977 Bearing Trees:

Utility Pole #N64-1314	N 52° W	49.81 feet
'X' chiseled in rock	S 57° W	35.93 feet

PEER REVIEW APPROVED

Gary L. Pisoni 12-18-98
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found. Found monument as described above, no evidence of reference objects. I accept the monument as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Utility Pole #94-03708	N 52° W	49.32 feet
County Road sign 1 1/2" dia. Pipe	N 44° E	34.70 feet
Rebar 5/8" x 30"	S 44° E	34.46 feet
Sugar Maple 16"	S 51° W	54.65 feet
Steel sign post	N 52° W	39.00 feet


98-141

Signed by Gary L. Pisoni

Date 12-21-98

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1971



L. 7 P. 293