

SURVEY & REMONUMENTATION

JAN 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY
 MICHIGAN
 RECEIVED FOR RECORD

97 DEC 23 PM 1:30
 L.C. Records L.7 P. 167

Gilbert Stiles
 REGISTER OF DEEDS

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>33W</u>	<u>E-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner Common to Sections 8, 9, 17, 16, T44N, R33W

I, Gary L. Pisoni, in a field survey on December 10, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5					●								
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Original corner established in 1851 by Guy H. Carleton, U.S. Deputy Surveyor.
 Original Corner: Wood Post
 Original Bearing Trees:

Sugar	12"	N 55° W	8 lks (5.28 feet)
White Pine	30"	S 84° E	30 lks (19.80 feet)

On 8/24/78, Author O. Enger RLS, DNR found a 3/4" dia. iron rod of unknown length located in the centerline of East Townline Road and a fence line running North and South. Position checks with other corners in the area. He accepted the iron rod and recorded said corner in Land Corner Certificate L.2b, page 12 on 3/10/80.

1978 Bearing Trees:

Power Pole	N38-2943	S 47 1/2° E	44.78 feet
Red Pine	6"	N 22° W	39.50 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

Found a 3/4" dia. iron rod as described above by Arthur Enger.

I accept the iron rod as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

PEER GROUP APPROVED

Gary L. Pisoni 12-19-97
 IRON COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described Section corner, set two reference monuments being a 2" dia. by 30" long aluminum pipe monument, 2" above ground surface with a 3" dia. aluminum cap stamped as follows: Iron County Remonumentation, T44N, R33W, R.M., S8, S9, S17, S16, 1997, RLS 27457, 34.09 ft, S 27° E and Iron County Remonumentation, T44N, R33W, R.M., S8, S9, S17, S16, 1997, RLS 27457, 34.26 ft, N37° E. Blazed and scribed the following new bearing trees: (Measurements taken to a nail in side of tree)

R.M.	2"x30" Al. Pipe	N 27° W	34.09 feet
Balsam	6"	N 16° E	43.37 feet
Utility Pole	90-21925	S 49° E	47.24 feet
R.M.	2"x30" Al. Pipe	S 37° W	34.26 feet
Steel sign post		N 27° W	35.25 feet
Steel sign post		S 37° W	35.06 feet

97-14a
 Signed by *Gary L. Pisoni*
 Surveyor's Michigan License No. 27457

Date December 16, 1997

