

SURVEY & REMONUMENTATION

JAN 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY
 MICHIGAN
 RECEIVED FOR RECORD

97 DEC 23 PM 1:31

L.C. Records L.P. 168

Gilbert Stobie
 REGISTER OF DEEDS

For corners in

<u>Iron</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>44N</u> R <u>33W</u>	<u>F-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Quarter Corner Between Sections 9 and 16, T44N, R33W.

I, Gary L. Pisoni, in a field survey on December 10, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5						●							
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Original Corner established in 1851 by Guy H. Carleton, U. S. Deputy Surveyor.
 Original Corner: Wood Post
 Original Bearing Trees:

Sugar	10"	N 31° W	30 lks (19.80 feet)
Sugar	10"	S 44° W	34 lks (22.44 feet)

PEER GROUP APPROVED

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Gary L. Pisoni 12-19-97
 ILM COUNTY REPRESENTATIVE

No evidence of original B.T.s found.

Corner position located at the intersection of a North-South fence line and the centerline of an East-West town road.

Accepted the corner position as the best available evidence for restoring the quarter corner.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a reference monument being a 2" dia. by 30" long aluminum pipe monument, 2" above ground surface with a 3" dia. aluminum cap stamped as follows: Iron County Remonumentation, T44N, R33W, R.M., 1/4, S9, S16, 1997 N 50° E, 32.13, RLS 27457

At the corner position, set a 2" dia. by 30" long aluminum pipe monument 6" below roadbed surface with a 3" dia. aluminum cap stamped as follows: Iron County Remonumentation, T44N, R33W, 1/4, S9, S16, 1997, RLS 27457 from which the following bear (Measurements are taken to a nail in side of tree)

Sugar Maple	14"	N 24° W	62.57 feet
Utility Pole	89-21305	N 14° E	29.15 feet
Utility Pole	N65-1363	S 69° E	83.01 feet
R.M.	2"x30" Al. Pipe	S 50° W	32.13 feet
Steel sign post		S 50° W	33.00 feet

97-15a
 Signed by Gary L. Pisoni
 Surveyor's Michigan License No. 27457

Date December 16, 1997

