

SURVEY & REMONUMENTATION

JAN 19 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>33W</u>	<u>F-7</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

98 DEC 28 AM 11:13

L.C. Records: L. 7, P. 252

Gilbert Stetson

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Quarter Corner between Section 16 and 21, T44N, R33W

I, Gary L. Pisoni, in a field survey on October 24, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7						●							
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in 1851 by Guy H. Carleton, U.S. Deputy Surveyor.
 Original Corner; Wood Post
 Original Bearing Trees:

Sugar	16"	N 40°E	10 lks (6.60 feet)
Fir	10"	S 14°E	15 lks (9.90 feet)

On 8-6-79 Arthur O. Enger, RLS found a 12" long Well Point in place, well point evidently in place for many years, and apparently used by State Highway Department and others, Origin unknown. Replaced well pipe with a 1" I.D. X 24" iron pipe with a 3 3/4" aluminum cap; stamped as follows: DNR, T44N, R33W, 1/4, S-16, S-21, 1979, RLS 13581 recorded in L.C. Certificate Liber 2b, Page 13.

1979 Bearing Trees:

Power Pole #85-8 (Mag.)	S 12°E	40.45 feet
Steel Stop Sign Post (Mag.)	N 09°E	85.90 feet
SE Cor. House Foundation (True)	N 82°32'W	128.76 feet
NE Cor. House Foundation (True)	N 54°57'W	157.96 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 No evidence of original B.T.s found.

Found monument as described above and the following reference objects:

SE Cor. House Foundation	N 85°W	128.79 feet
NE Cor. House Foundation	N 58°W	157.98 feet

PEER GROUP APPROVED
Iron S. Pisoni 11-24-98
 COUNTY REPRESENTATIVE

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 From the above described monument blazed and scribed the following bearing trees: (All measurements taken to a nail in side of tree)

Utility Pole #94-03702	N 58° E	106.37 feet
Red Pine 12"	S 14° W	46.54 feet
Steel sign post	North	0.89 feet

98-69
 Signed by Gary L. Pisoni Date 12-21-98
 Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1995



1.7 P. 252