

**SURVEY &  
REMONUMENTATION**

JAN 19 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>33W</u>	<u>G-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

98 DEC 28 AM 11:13  
L.C. Records: L. 7, P. 250  
*Gary L. Pisoni*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Quarter Corner Sections 21 and 22, T44N, R33W

I, Gary L. Pisoni, in a field survey on October 24, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established in June, 1851 by Guy H. Carleton, U.S. Deputy Surveyor.

Original Corner; Wood Post  
Original Bearing Trees:

Yellow Birch	--	S 52° E	42 lks (27.72 feet)
Sugar	16"	N 12° W	27 lks (17.82 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

Found an iron pin located in the centerline of a North/South county road, 3" below road bed surface and located on an East/West old fence line. Corner has been in existence for over 25 years and has been used for many surveys throughout the area. I accept the iron pin as the best available evidence for restoring the corner position.

Distances to the North and South check will with GLO distances.

Corner record research on file with County Representative.

PEER GROUP APPROVED  
*Gary L. Pisoni 11-24-98*  
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Set two (2) reference monuments being a 5/8" diameter by 30" long rebar pin with a 3" diameter aluminum cap stamped as follows: Iron County Remonumentation, T44N, R33W, R.M., 1/4, S-21, S-22, West, 36.18 feet 1998, RLS 27457; T44N, R33W, R.M., 1/4, S-21, S-22, N 45° E, 50.07 feet 1998, RLS 27457 from which I established the following new blazed and scribed bearing trees: (All measurements taken to a nail in side of tree)

Sugar Maple (tpl)	9"	N 55° E	83.38 feet
R.M.	5/8" x 30" rebar	East	36.18 feet
R.M.	5/8" x 30" rebar	S 45° W	50.07 feet
Sugar Maple	11"	N 41° W	75.20 feet
Steel sign post		East	37.68 feet

98-72  
Signed by Gary L. Pisoni Date 12-21-98

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
27457 REVISION MAY 14, 1975  
REVISION JAN., 1983  
REVISION OCT., 1995



L. 7 P. 250