

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 32 T 44N R 33W	3
	S 32 T 44N R 33W	8
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 3 09/08/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(3-Sec. 32) North 1/16 corner between Sections 31 and 32. 1978 - Established by A.O.Enger RLS on line between Sec. Cor. 20.164 ch. N and 1/4 Cor. 20.164 ch. S. Set 1"IDx36" I.pipe with 3 3/4" aluminum cap. Sugar Maple 14" S54W 22.8', W.Pine 32" S25E 29.3'.

(8-Sec. 32) West 1/16 corner Section 32. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(3-Sec. 32) Found the 1978 monument in good condition and at record bearing and distance from the remaining 1978 witness W.Pine 30" found in good condition. The Maple BT SW was not recovered. The monument is located substantially midway and on line between Section and Quarter corners and I accept same as a careful and faithful establishment of the position of the corner.

(8-Sec. 32) Established the corner midway and on a straight line between Quarter corner 1321.03' west and Center of Section 1321.03' east. From the position thus established, I found a 1.25" steel pin, placed by persons unknown, N1E 23.2' distant, which I did not accept as marking the position for the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(3) Fd. 1"ID I.pipe with 3 3/4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 30" W.Pine S22E 30.5' old blazes 1978 BT
 9" Sugar N02E 11.7' mrkd "1/16S BT"
 5" Sugar N58E 19.6' do
 10" Sugar S86W 21.2' do
 Sq'd Cedar post adjacent.
 Bearings are magnetic.

(8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 6" Sugar N26E 32.5' mrkd "1/16S BT"
 8" Sugar S62E 41.8' do
 6" twin Maple S27W 24.3' do
 9" Sugar N31W 19.85' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/21/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

