

**LAND CORNER RECORDATION CERTIFICATE**  
 Filling Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 44N R 33W	D11
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 32 T 44N R 33W	11
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11		●											
12	31	●	32	33	34	35	36						
13													

I, Stephan J. Szyszkoski, in a field survey on 11 09/03/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 (D11) Quarter corner common to Sections 29 and 32. 2005 - Corner of record approved by Iron County Peer Group Liber 11 Page 294, Iron County Land Corner Records. Recorded by Robert A. Goodreau RLS. Found 1" iron pipe with 3 3/4" alum. MDNR cap placed by A.O.Enger RLS in 1978. 26" W.Pine N11E 80.28', 12" B.Spruce S10E 43.70', 7" Balsam S42W 4.99', 5" Balsam N82W 28.45', Steel sign post North 1.05'.

(11-Sec. 32) Southwest 1/16 corner, Section 32. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 (D11) Found the monument of record in good condition and at record bearing and distance from the 2005 witnesses. The W.Pine NE is in good condition, the B.Spruce SE has been uprooted, the Balsam NW is in good condition, the Balsam SW was cut down to facilitate GPS observations this date, the steel sign post is in place. Made new witnesses as described below.

(11-Sec. 32) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 (D11) Fd. 1"ID I.pipe with 3 3/4" alum. MDNR cap. Set meas. nail with MDNR tag in:  
 5" Maple S19W 39.6' mrkd "1/4S NBT"  
 4" Maple S83W 31.3' do  
 2005 wits:  
 24" W.Pine N15E 80.2' mrkd "1/4S NBT"  
 5" Balsam N81W 28.4' blazed, no scribing  
 Steel sign post North 1.05'  
 Bearings are magnetic.

(11) Set 1"ID I.pipe with 4" alum. MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 7" Spruce N74E 27.3' mrkd "1/16S BT"  
 7" Spruce S28W 25.2' do  
 6" Spruce N53W 34.0' do  
 8" Spruce N27W 32.3' do  
 Set sq'd Cedar post adjacent.  
 Bearings are magnetic.

Signed by *Stephan J. Szyszkoski* Date 10/21/2008  
 Surveyor's Michigan License No. 33986  
 For the Michigan Department of Natural Resources, Office of Land and Facilities

