

LAND CORNER RECORDATION CERTIFICATE
Feeling Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>32</u> T <u>44N</u> R <u>33W</u>	<u>9</u>
	S <u>32</u> T <u>44N</u> R <u>33W</u>	<u>12</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 9 09/08/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(9-Sec. 32) East 1/16 corner, Section 32. Not established in the original survey.

(12-Sec. 32) South 1/16 corner, Section 32. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(9-Sec. 32) Established the corner midway and on a straight line between Center of Section 1302.44' West and Quarter corner 1302.44' East.

(12-Sec. 32) Established the corner midway and on a straight line between Center of Section 1328.32' north and Quarter corner 1328.32' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 12" Spruce S05W 19.5' mrkd "1/16S BT"
 3" Balsam S76W 4.8' do
 13" Spruce N57W 16.3' do
 6" Poplar N25W 29.4' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

(12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 7" Maple N35E 37.8' mrkd "1/16S BT"
 11" Spruce S60W 25.1' do
 6" B.Ash N79W 12.5' do
 7" twin Maple N25W 43.2' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/21/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

