

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 44N R 33W	D13
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 32 T 44N R 33W	5
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 5 09/09/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(D13) Corner common to Section 32 T44N-R33W and Section 5 T43N-R33W. 2005 - Corner of record approved by Iron County Peer Group and recorded in Liber 11 Page 295, Iron County Land Corner Records. Remonumented by Robert A. Goodreau RLS at the position established by A.O.Enger RLS in 1975. Set 5/8"x24" bar with 3" aluminum cap. 17" Maple S31W 11.83', 8" Maple N21E 35.40', 8" Maple N59E 21.58', 6" Poplar N70W 22.30', Steel sign post North 1.3'.

(5-Sec. 32) North 1/16 corner, Section 32. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D13) Recovered the 2005 monument in good condition and at record bearing and distance from the 2005 accessories, all in good condition but for the Poplar N70W 22.30', which is standing dead. Accepted the monument and made one new witness as described below.

(5-Sec. 32) Established the corner midway and on a straight line between Quarter corner 1327.86' north and Center of Section 1327.86' south. From the position for the corner, I found a 1.25" dia. steel pin, placed by persons unknown, N54W 16.8' distant, which I did not accept as marking the position for the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D13) Found 5/8" bar with 3" aluminum cap as recorded L.11 P.295. Found witnesses as recorded.
 Set measuring nail with MDNR tag in the side of:
 4" Poplar N49W 5.2' mrkd "1/4S NBT"
 Bearings are magnetic.

(5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 9" W.Pine N27E 24.85' mrkd "1/16S BT"
 4" Spruce N79E 21.3' do
 9" Maple S66E 39.65' do
 4" Spruce S20E 16.4' do
 Set sq'd Cedar post adjacent. Sq'd a 4" Balsam N66W 1.6'. Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/21/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities