

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 32 T 44N R 33W	D12
	S 32 T 44N R 33W	4
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

D12 09/03/2008

I, Stephan J. Szyszkoski, in a field survey on 4 09/09/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(D12) Center of Section 32. Not established in the original survey.

(4-Sec. 32) Northwest 1/16 corner, Section 32. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D12) Established the corner at the intersection of straight lines connecting opposite Quarter corners. From the position thus established, I found a 1.25" dia. steel pin, placed by persons unknown, N8E 27.2' distant, which I did not accept as marking the position for the corner.

(4-Sec. 32) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 9" Spruce S76W 37.55' mrkd "C1/4 BT"  
 4" Spruce N29E 20.8' do  
 7" Spruce N72E 14.9' do  
 3" Spruce S44E 21.1' do  
 Set sq'd Cedar post adjacent.  
 Bearings are magnetic.

(4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 5" Spruce N08E 61.55' mrkd "1/16 BT"  
 8" Sugar N89E 25.7' do  
 3" Sugar S54E 13.9' do  
 8" twin Maple S11E 45.6' do  
 Set sq'd Cedar post adjacent.  
 Bearings are magnetic.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2			1
3													
4		7		8		9		10		11			12
5													
6		10		17		16		15		14			13
7													
8		19		20		21		22		23			24
9													
10		30		29		28		27		26			25
11													
12		31		32		33		34		35			36
13													

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 10/21/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

