

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>32</u> T <u>44N</u> R <u>33W</u>	<u>6</u>
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 09/08/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(6-Sec. 32) Northeast 1/16 corner, Section 32. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(6-Sec. 32) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. The position for the corner falls in a flooded area and is not accessible. Placed two WITNESS CORNERS on the 1/16 lines 100.00 ft. West of the corner position and 435.00 ft. South of the corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap for a WITNESS CORNER 100.00' West of the corner position and on the 1/16 line.
 Set measuring nail with MDNR tag in the side of:
 4" Balsam S28W 50.2' mrkd "WC BT"
 17" W.Pine S69W 47.3' (slope) do
 14" Spruce S70W 53.1' (slope) do
 5" Balsam N68W 39.9' do
 Set sq'd post adjacent. Bearings magnetic.

(6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap for a WITNESS CORNER 435.00' South of the corner position and on the 1/16 line.
 Set measuring nail with MDNR tag in the side of:
 4" Balsam N07E 16.0' mrkd "WC BT"
 3" Balsam N70E 5.25' do
 3" Balsam S17E 7.1' do
 3" Cherry N36W 8.25' do
 Set sq'd post adjacent. Bearings magnetic.

Signed by *Stephan J. Szyszkoski*
 Surveyor's Michigan License No. 33986

Date 10/21/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

