

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>44</u> N. <u>X</u> , R. <u>34</u> E. <u>W.</u>	G8
2. PROPERTY CONTROL- 22 ING IN SECTION_____	, T. <u>44</u> N. <u>X</u> , R. <u>34</u> E. <u>W.</u>	3
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. _____, R. _____ E. <u>W.</u>	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 26, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner G8 (1/4 corner between Sections 21 & 22, T44N, R34W):
 Wood post (Not found. No subsequent monuments found.)
 Sugar 16 N35W 41 (" " " " accessories ")
 Sugar 14 S40E 31 (" " " " " ")

Corner 3 (North 1/16 corner between Sections 21 & 22, T44N, R34W):
 Not established in original survey, and erroneously, subsequently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner G8: Re-established on line between Sec. Corners 39.934 ch. to N and to S.
Corner 3: Established on line between Sec. Corner 19.967 ch. N and 1/4 cor. 19.967 ch. S. Found a 3"x3"x5' squared cedar post N52°E 76.3 ft. for a forester's approx. corner, evidently set by measuring S from an old Land Economic Survey control post mistakenly assumed to be the sec. corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner G8: 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.
 Sugar Maple 6 N64°W (mag.) 13.4 ft. "1/4S, NBT"
 Sugar Maple 5 S18°W (mag.) 23.1 ft. "1/4S, NBT"
 Declination 0°30' East

Corner 3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Sugar Maple 8 S25°E (mag.) 17.0 ft. "1/16S, BT"
 Sugar Maple 8 N62°W (mag.) 21.4 ft. "1/16S, BT"
 Declination 1°30' East

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August

CHIEF OF SURVEY PARTY
Arthur O. Enger
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

